

REGIONAL REVIEW NOTIFICATION

Atlanta Regional Commission • 229 Peachtree Street NE | Suite 100 | Atlanta, Georgia 30303 • ph: 404.463.3100 fax: 404.463.3205 • atlantaregional.org

DATE: February 27, 2023

TO: Chairwoman Nicole Love Hendrickson, Gwinnett County

ATTN TO: Sushmita Arjyal, Current Planning Supervisor, Gwinnett County

RE: Development of Regional Impact Review

FROM: Mike Alexander, Director, ARC Center for Livable Communities

ARC has completed a preliminary regional review of the following DRI. ARC reviewed the DRI's relationship to regional plans, goals and policies – and impacts it may have on the activities, plans, goals and policies of other local jurisdictions as well as state, federal and other agencies. This preliminary report does not address whether the DRI is or is not in the best interest of the local government.

Name of Proposal: Brand Properties Hamilton Mill DRI 3812

Submitting Local Government: Gwinnett County

Date Opened: February 27, 2023 Comments: March 14, 2023 Date to Close: March 15, 2023

<u>Description</u>: A DRI review of a proposal to construct a mixed-use development with 700 multifamily units and 17,000 square feet of commercial space on a 79-acre site off Sardis Church Road in unincorporated Gwinnett County.

PRELIMINARY COMMENTS:

Key Comments

The Atlanta Region's Plan assigns the Developing Suburbs growth management designation to the project site. The project is partially aligned with Developing Suburbs policy recommendations which state "There is a need in these areas for additional preservation of critical environmental locations and resources, as well as agricultural and forest uses." It could be better aligned through retention of additional undisturbed areas.

The project's provision of retail space that can serve the project residents as well as outside customers is supportive of mixed-use regional growth policies.

The project is expected to generate approximately 4,297 net new daily vehicular trips; a range of roadway improvements are proposed in the TIS to mitigate generated vehicular traffic.

A total of 2,250 parking spaces are provided which is marginally more than the number required. Regional multi-modal transportation policies are supportive of reduced parking and a modest parking reduction may be warranted.

No EV charging spaces appear to be identified; provision of adequate EV charging spaces would be supportive of regional EV infrastructure policies.

The Gwinnett County trails Master Plan shows a priority trail that is planned on Hamilton Mill Road. The inclusion of this trail component in the project is supportive of regional multi-modal transportation policies.

Incorporation of green stormwater and heat island mitigation designs for the large number of surface car parking spaces proposed would be supportive of regional environmental policies.

General Comments

The Atlanta Region's Plan, developed by ARC in close coordination with partner local governments, is intended to broadly guide regional development in the 12-county metro region to ensure that required infrastructure and resources are in place to support continued economic development and prosperity. The Plan assigns a relevant growth management category designation with accompanying policy recommendations to all areas in the region. This DRI site is designated Developing Suburbs; associated policy recommendations are provided at the end of these comments.

The project's inclusion of 17,000 SF of retail space offers some opportunity for reduced car trips and increased walkability if tenants provide goods and services utilized by residents.

<u>Transportation and Mobility Comments</u>

ARC's Transportation Access and Mobility Group comments will be provided in the Final Report.

Regional multi-modal transportation policies are supportive of reduced parking and a modest parking reduction may be warranted.

No EV charging spaces appear to be identified; provision of adequate EV charging spaces would be supportive of regional EV infrastructure policies.

The project is expected to generate approximately 4,297 net new daily vehicular trips; a range of roadway improvements are proposed in the TIS to mitigate generated vehicular traffic.

The Gwinnett County trails Master Plan shows a priority trail that is planned on Hamilton Mill Road. The inclusion of this trail component in the project is supportive of regional multi-modal transportation policies.

Care should be taken to ensure that the constructed development provides an interconnected, functional, clearly marked and comfortable pedestrian experience on all driveways, paths, entrances, and parking areas. To the maximum extent possible, new driveways and intersection corners where pedestrians will cross should be constructed with minimal curb radii to reduce speeds of turning vehicles and decrease crossing distances for pedestrians.

ARC Natural Resources Comments

ARC's Natural Resources Group comments will be provided in the Final Report.

Other Environmental Comments

A significant amount of forested stream and wetland buffer area is proposed to be retained. Additional retention of these areas would be desirable and in keeping with regional goals regarding carbon sequestration and climate change/heat island effect mitigation. Designation of this area as managed open/conservation space could meaningfully reduce the overall impact of the project.

The project can support The Atlanta Region's Plan in general by incorporating other aspects of regional policy, including green infrastructure and/or low-impact design, e.g., pervious pavers, rain gardens, vegetated swales, etc., in parking areas and site driveways, and as part of any improvements to site frontages.

Incorporation of green stormwater and heat island mitigation designs for the large number of surface car parking spaces proposed and use of an ecosystem-based design for the two stormwater detention areas would be supportive of regional environmental policies.

Atlanta Region's Plan Growth Policy Considerations: Developing Suburbs

The Atlanta Region's Plan identifies Developing Suburbs as areas in the region where suburban development has occurred, and the conventional development pattern is present but not set. These areas are characterized by residential development with pockets of commercial and industrial development. These areas represent the extent of the urban service area. There is a need in these areas for additional preservation of critical environmental locations and resources, as well as agricultural and forest uses. Limited existing infrastructure in these areas will constrain the amount of additional growth that is possible. Transportation improvements are needed within these Developing Suburbs, but care should be taken not to spur unwanted growth.

The project is partially aligned with Developing Suburbs policy recommendations which state "There is a need in these areas for additional preservation of critical environmental locations and resources, as well as agricultural and forest uses." It could be better aligned through retention of additional undisturbed areas and utilization of green infrastructure in surface parking areas. Henry County leadership and staff, along with the applicant team, should collaborate closely to ensure optimal sensitivity to the needs of nearby local governments, neighborhoods, and natural systems.

THE FOLLOWING LOCAL GOVERNMENTS AND AGENCIES RECEIVED NOTICE OF THIS REVIEW:

ATLANTA REGIONAL COMMISSION
GEORGIA DEPARTMENT OF TRANSPORTATION

CITY OF FLOWERY BRANCH

GEORGIA DEPARTMENT OF NATURAL RESOURCE
GEORGIA REGIONAL TRANSPORTATION AUTHORITY

GEORGIA DEPARTMENT OF COMMUNITY AFFAIRS
GEORGIA SOIL AND WATER CONSERVATION COMMISSION

GEORGIA ENVIRONMENTAL FINANCE AUTHORITY BARTOW COUNTY CITY OF AUBURN GEORGIA CONSERVANCY CITY OF DACULA CITY OF BUFORD HALL COUNTY
CITY OF BRASELTON
CITY OF LAWRENCEVILLE

For questions, please contact Donald Shockey at (470) 378–1531 or dshockey@atlantaregional.org. This finding will be published to the ARC review website located at http://atlantaregional.org/plan-reviews.






Developments of Regional Impact

DRI Home <u>Tier Map</u> <u>Apply</u> <u>View Submissions</u> <u>Login</u>

DRI #3812 DEVELOPMENT OF REGIONAL IMPACT Initial DRI Information This form is to be completed by the city or county government to provide basic project information that will allow the RDC to determine if the project appears to meet or exceed applicable DRI thresholds. Refer to both the Rules for the DRI Process and the DRI Tiers and Thresholds for more information. **Local Government Information** Submitting Local Gwinnett Individual completing form: Catherine Long Telephone: 678.518.6106 E-mail: catherine.long@gwinnettcounty.com *Note: The local government representative completing this form is responsible for the accuracy of the information contained herein. If a project is to be located in more than one jurisdiction and, in total, the project meets or exceeds a DRI threshold, the local government in which the largest portion of the project is to be located is responsible for initiating the DRI review process. **Proposed Project Information** Name of Proposed Project: Brand Properties Hamilton Mill Location (Street Address, 3527 Sardis Church Road GPS Coordinates, or Legal Land Lot Description): Brief Description of Project: mixed use development including 17,000 square feet of commercial space and 700 multifamily units **Development Type:** Hotels Wastewater Treatment Facilities (not selected) Office Mixed Use Petroleum Storage Facilities Commercial Airports Water Supply Intakes/Reservoirs Wholesale & Distribution Attractions & Recreational Facilities Intermodal Terminals Hospitals and Health Care Facilities Post-Secondary Schools Truck Stops Housing Waste Handling Facilities Any other development types Ondustrial Quarries, Asphalt & Cement Plants If other development type, describe: Project Size (# of units, floor 1,000 square feet commercial and 700 multifamily units Developer: Brand Properties Mailing Address: 3328 Peachtree Road NE Address 2: City:Atlanta State: GA Zip:30326 Telephone: 770.497.6474 Email: jbarge@brandproperties.com (not selected) Yes No from developer/applicant? If yes, property owner: Jackson EMC Is the proposed project (not selected) Yes No entirely located within your



GRTA DRI Page | ARC DRI Page | RC Links | DCA DRI Page

DRI Site Map | Contact





Developments of Regional Impact

DRI Home

Tier Map

Apply

View Submissions

<u>Login</u>

DRI #3812

DEVELOPMENT OF REGIONAL IMPACT Additional DRI Information

This form is to be completed by the city or county government to provide information needed by the RDC for its review of the proposed DRI. Refer to both the Rules for the DRI Process and the DRI Tiers and Thresholds for more information.

Local Government Information

Submitting Local Gwinnett

Government:

Individual completing form: Sushmita Arjyal

Telephone: 678.518.6255

Email: sushmita.arjyal@gwinnettcounty.com

Project Information

Name of Proposed Project: Brand Properties Hamilton Mill

DRI ID Number: 3812

Developer/Applicant: Brand Properties

Telephone: 770.497.6474

Email(s): jbarge@brandproperties.com

Additional Information Requested

Has the RDC identified any additional information

required in order to proceed with the official regional

(not selected) Yes No

review process? (If no, proceed to Economic

Impacts.)

If yes, has that additional information been provided

(not selected) Yes No

to your RDC and, if applicable, GRTA?

If no, the official review process can not start until this additional information is provided.

Economic Development

Estimated Value at Build-

\$200,000,000

Estimated annual local tax revenues (i.e., property tax, sales tax) likely to be

\$3,000,000

generated by the proposed

development:

Is the regional work force sufficient to fill the demand created by the proposed

displace any existing uses?

(not selected) Yes No

project? Will this development

(not selected) Yes No

If yes, please describe (including number of units, square feet, etc):

Water Supply

Name of water supply provider for this site:


Gwinnett County

What is the estimated water supply demand to be generated by the project, measured in Millions of Gallons Per Day (MGD)?	0.102 MGD	
Is sufficient water supply capacity available to serve the proposed project?	(not selected) Yes No	
If no, describe any plans to e	expand the existing water supply capacity:	
Is a water line extension required to serve this project?	(not selected) Yes No	
il yes, now much additional	line (in miles) will be required?	
Wastewater Disposal		
Name of wastewater treatment provider for this site:	Gwinnett County	
What is the estimated sewage flow to be generated by the project, measured in Millions of Gallons Per Day (MGD)?	0.155 MGD	
Is sufficient wastewater treatment capacity available to serve this proposed project?	○(not selected) Yes No	
If no, describe any plans to expand existing wastewater treatment capacity:		
Is a sewer line extension required to serve this project?	(not selected) Yes No	
If yes, how much additional li	ine (in miles) will be required?	
Land Transportation		
How much traffic volume is expected to be generated by the proposed development, in peak hour vehicle trips per day? (If only an alternative measure	Daily Trips: 4,297; AM Peak Hour Trips: 91 entering, 247 exiting; PM Peak Hour Trips: 226 entering, 161 exiting	
of volume is available, please provide.) Has a traffic study been performed to determine		
whether or not transportation or access improvements will be needed to serve this project?	(not selected) Yes No	
Are transportation improvements needed to serve this project?	(not selected) Yes No	
If yes, please describe below:See the detailed traffic study for more information		
Solid Waste Disposal		
How much solid wasts is 45-	·	
How much solid waste is the project expected to generate annually (in tons)?	800	
Is sufficient landfill capacity available to serve this proposed project?	(not selected) Yes No	
If no, describe any plans to expand existing landfill capacity:		
Will any hazardous waste be generated by the development?	(not selected) Yes No	
If yes, please explain:		
Stormwater Management		
What percentage of the site is projected to be impervious surface once the	41%	

proposed development has been constructed?	
project's impacts on stormwa Stormwater Management Ma	sosed (such as buffers, detention or retention ponds, pervious parking areas) to mitigate the ater management: The project will be designed in compliance with the Gwinnett County anual, including measures for runoff reduction/water quality (bio-retention, permeable otection/flood protection using above-ground detention ponds.
	Environmental Quality
Is the development located w	vithin, or likely to affect any of the following:
Water supply watersheds?	(not selected) Yes No
Significant groundwater recharge areas?	○(not selected)○Yes◎No
3. Wetlands?	(not selected) Yes No
4. Protected mountains?	(not selected) Yes No
5. Protected river corridors?	(not selected) Yes No
6. Floodplains?	(not selected) Yes No
7. Historic resources?	(not selected) Yes No
8. Other environmentally sensitive resources?	(not selected) Yes No
	uestion above, describe how the identified resource(s) may be affected: stream and associated wetlands will occur due to roadway crossings. All applicable permits cts.
Back to Top	

GRTA DRI Page | ARC DRI Page | RC Links | DCA DRI Page

DRI Site Map | Contact



3500 Parkway Lane Suite 500 **Peachtree Corners** Georgia 30092

Copyright © 2023 by Pond & Company. All rights reserved. No copying or duplication of these documents is allowed without the expressed written agreement of Pond & Company.

DPR SEAL

CLIENT INFORMATION

PROJECT NAME

BRAND PROPERTIES HAMILTON

2549 HAMILTON MILL RD., BUFORD, GA. 30519

DRI 3812

DRAWING ISSUE

DRAWN BY: CHECKED BY: 1/19/2023 P220779 PROJECT#

DESIGNED BY

SHEET TITLE

DRI SITE PLAN

DRI 3812

SHEET NUMBER

CS-101

ORIGINAL SHEET SIZE: 22" X 34"

DRI SUBMITTAL