

Transportation Investment Act of 2010 Final Investment List Project Fact Sheet (FINAL - January 2012)*

Identification	TIA-M-001	Location: Regional
Project Name	MARTA Train Control Systems Upgrade	Northwest 575 and Zalife
Project Type	Transit	85
	□ Road Capacity Expansion □ Road Asset Management □ Road Safety / Operations □ Freight / Logistics □ Aviation □ Bicycle / Pedestrian □ Transit Network Expansion □ Transit Operations / Maint.	20 20 East
PLAN 2040 Status	Not identified as a line item in PLAN 2040, but consistent with plan emphasis on preservation of existing transit services Related Project Numbers: N/A	South South
Description, Purpose and	This project will upgrade MARTA's train control system and its supervisory control and or project will integrate the various elements of the train control system into a single platform that directly in the control center. The project will create a single integrated platform that directly in the control center.	orm for ease of use, efficiency and to eliminate

Benefits

power, provides precision docking, train approaching lights, and monitors other auxiliary functions, and it will also replace current controls systems at all MARTA yards and establish new Rail Services Control and Back-Up Control Centers. This project could also lay the foundation for a regionally integrated control center capable of accommodating the train control systems for future light rail, commuter and bus rapid transit services. The precision docking component will upgrade MARTA's entire rail fleet and wayside equipment to allow trains to stop at pre-marked locations on the platforms. All rail cars will be upgraded to latest technology to communicate with the wayside for precision stopping. Platforms will be appropriately marked to indicate the location of car doors. Total TIA funding committed to the project is 4,440,000, with additional funds from other MARTA revenue sources likely to complement this investment.

Project Length

Lanes (Current)

N/A Lanes (Proposed)

N/A

N/A

Funding Commitments (all amounts shown in current year 2011

dollars)

TIA Funds \$4,440,000 Federal Funds \$0 Local Funds* \$0 **Total Funding** \$4,440,000

miles

These fields

applicable to

certain types

of projects.

are only

* Additional local funds may be identified prior to the referendum to deliver some projects.

Implementation Band

Construction likely to occur during all bands (2013-2022)



^{*} This fact sheet provides supplemental scope information related to projects approved by the Atlanta Regional Roundtable on October 13, 2011. For certain project types, it may also include performance data derived through a technical analysis conducted by the Atlanta Regional Commission following approval of the investment list. Grammatical corrections and clarifications were also made to the text as necessary. No changes to project scopes, schedules or budgets were made. For the original fact sheets, as approved by the Roundtable, refer to the Final Report available at www.atlantaregionalroundtable.com.